

PROJECT SCOPE
For
City of Medina Job No. 1165: 2024 CONCRETE PAVEMENT JOINT SEALING PROGRAM

General

This Project consists of the cleaning and preparation of the joints/cracks for sealant, furnishing and placement of joint sealant for concrete pavement joints and cracks, protection of joint sealant until sealant has cured, and all necessary traffic control. Joint and crack sealing will be completed at various locations throughout the City of Medina.

Some joints and all random cracks will be saw cut prior to placement of sealant. In addition, all cracks must be thoroughly cleaned utilizing pressurized compressed air prior to receiving sealant. The bid form includes unit price items for joint sealant as well as for saw cutting.

Traffic control is required.

Bid Information

The Bid includes a base bid only. A summary of the base bid is as follows:

- **BASE BID:**
The base bid includes furnishing and installing approximately 18,393 pounds of Type II crack sealant. There will be approximately 44,860 lineal feet of joints and cracks to be sealed, of this amount, the bid includes saw cutting/routing of approximately 6,729 lineal feet of joints and cracks prior to applying joint sealant. The balance remaining (approximately 38,131 lineal feet) must be cleaned and prepared but do not have to be saw cut/routed.

General Notes

The Bidders attention is directed to the project specifications which have been modified from previous year's programs'. Specifically:

- Saw cutting of some of the joints and cracks prior to applying sealant is required. Saw cutting of joints and cracks will be a stand alone unit price item. Please refer to the project specifications for details.
- Saw cutting must be completed with a mechanically driven saw designed for cutting concrete pavement using diamond tipped concrete saw blades. Routing of concrete joints with a router is NOT acceptable.

Prevailing Wage

Prevailing Wage Rates WILL apply to this project. All labor utilized for this project for both the general contractor and any sub-contractor must be paid in strict compliance with the State of Ohio Prevailing Wage Rates. Please refer to Section 6. Prevailing Wage Rates of the Contract Documents for additional information.

Completion Date, Construction Phasing and Liquidated Damages

This project must be completed no later than June 30, 2025. Please note, Bidders will be permitted an opportunity to submit an earlier completion date if they choose. Bidders are advised that completion date may be a factor considered by the City of Medina when assessing the bids received. It is possible that a bidder with an early completion date may be awarded this contract even if that bid is not the lowest (responsive) bid received. Liquidated Damages in the amount of \$250 per calendar day will apply.

Pre-Bid Meeting

A non-mandatory pre-bid meeting will be held at 10:00 A.M. Wednesday, December 4, 2024 at Medina City Hall (132 N. Elmwood Avenue, Medina, Ohio 44256). Bidders are not required to attend the meeting in order to submit a bid.

Bid and Award Date

Bids will be accepted until 10:00 A.M. Wednesday, December 11, 2024, at which time they will be opened and read publicly. The City anticipates awarding the contract on December 16, 2024, and issuing a notice to proceed no later than December 30, 2024. The City of Medina reserves the right to reject any and all bids and to waive any informalities or irregularities in the bid.

Questions and Requests for Information

Questions and Requests for Information (RFI's) shall be submitted as follows:

Patrick Patton,
City of Medina, Ohio
132 N. Elmwood Avenue
Medina, Ohio 44256

Office: (330) 721-4721
Email: ppatton@medinaoh.org